

Low Energy Data Centre

Final Presentation

Group D

MURILO PEIXOTO
YASMINE TRIKI
RAFAEL SANTIAGO
LOÏC VAUTRIN

Design Brief


2

- ▶ Data centre 5 MW
- ▶ Reference for future
- ▶ Local building materials
- ▶ Innovative design
- ▶ PassivHaus standard
- ▶ PUE




Final 2D model

3



Final 3D model

4




Sizing

- ▶ 1232 racks
- ▶ 4 kW per rack
- ▶ Total area for servers: 2862 m²
- ▶ Open spaces for psychological comfort
- ▶ 90 employees
- ▶ Total area 1216 m²



5




Materials

6

► Server room

Material	Lamb's wool and bricks
Average Thermal conductivity[W/m.K]	0.02

► Facilities



Guarantee $U < 0.15 \text{ W/m}^2\text{K}$
With wall 40 cm thick

Lighting

7


Server Room

- ▶ 2460 Ceiling Smart LED (10 W)
- ▶ 526 lux



Facilities

- ▶ 162 Ceiling Smart LED (45 W) for the open space , 2 LED in each cellular offices.
- ▶ 423 Lux



Lighting

8

- ▶ Lights with presence control and natural light to reduce energy use
 - ▶ Reduction of 50% in energy use for lighting
 - ▶ Savings of £5400,00 a year
- ▶ Building design optimised for natural light

Safety

9


Security

- ▶ Security offices
- ▶ CCTV
- ▶ Access control with electronic card



Fire System

- ▶ Multi point very early smoke detection
- ▶ Exctinction by inert gas



Cooling

10

- ▶ Methodology: rack density:


$$P_{cooling} = \frac{P_{server} + P_{heat\ gains}}{n^{\circ}\ of\ servers}$$

- ▶ Expansion Plan: 50% $\rightarrow P_{server} = 7.5\text{MW}$
- ▶ $n^{\circ}\ of\ servers = 1232$
- ▶ $P_{heat\ gains} = 15.2\text{ kW}$
- ▶ Rack Density: $P_{cooling} = 6.1\text{ kW/rack}$

Ventilation

11


► Cold and Hot Aisle Isolation



Ventilation


12

- ▶ Final ventilation plans
 - Server cooling Mass Rate: (ASHRAE Recommendation): 0.4223 kg/s.rack
 - Server Inlet air temperature: 18°C . Outlet air temperature: 34.7°C
 - Air flow in the office: (0.45 Kg/s Recommendation)
 - Air flow(Real): If heating: 0.65 Kg/s . If cooling: 1.35 Kg/s .




Psychrometric Bin Analysis – from Falkirk

13



Cooling viability


14



PUE

15

- For high efficient datacentre <1.2



Technology

16


coolers							
AFL34R220							
air flow/rack m ³ /s	power/rack W	total power	total airflow (m ³ /s)	power/cooler W	airflow/cooler m ³ /s	number of coolers using power	number of coolers using air flow
0.344772	6100	7515200	424.7591	220000	30.9	34.16	12.4344
for N+1	36coolers						



humidifier				
ENS 18 30 960				
Worst case humidity Kg_water/kg_air	Minimum required Kg_water/kg g_air	Total Air flow kg/h	Water added Kg_water/h	Water/humidifier kg_water/h
0.0013348	0.0063	1873188	9300.751	18
total	517humidifiers			

Energy spent in the server room


17



Energy and costs for running the office

18


Energy savings in the office



Energy savings in the office

19

Energy spent in the office



Hot water supply

20


- ▶ Hot water 40°C, occasionally heated to 60°C.
- ▶ 55l/person/day -> 1200l storage.
- ▶ 87% to 99% of hot water supplied by solar. (142m² of SPC)
- ▶ Biomass boiler will supply the rest and heat water to 60°C



21

- Savings of 14%

total energy in 1 year			total cost	
data centre	52366	MW.h	4189280	pounds
solar	7527.656	MW.h	602212.4	pounds
savings	14.37508229		%	



Conclusion




22

- ▶ 99% of free cooling
- ▶ PUE=1.2
- ▶ Tier 4 standard
- ▶ 100% office heating
- ▶ Amount of renewables used



Thanks for your attention.

Any Questions ?

Web Site



24



Backup power

25

- ▶ Diesel generators
- ▶ 1.5 MW generators
- ▶ N+1=5 generators

